

APTER POWER INSTALLATION & VERIFICATION REFERENCE

6ES7288-2DT16-0AA0

A separate model-specific field checklist

Use this reference to verify the exact Siemens component before installation, substitution, or recommissioning. It intentionally does not repeat unconfirmed values.


Manufacturer	Siemens
Prepared by	Apter Power
Document ID	AP-SIE-08-6ES7288-2DT16-0AA0-IV-R1
Revision	R1
Issue date	2026-08-19

APTER POWER SALES TEAM

INDUSTRIAL AUTOMATION PRODUCT SUPPORT

Eight sensed states. Eight fast commands. One compact I/O bridge.

WHATSAPP / PHONE +86 180 3023 5313
EMAIL sales13@apterpower.com
WEBSITE www.apterpower.com



SCAN FOR PRODUCT & QUOTE
6ES7288-2DT16-0AA0

1. Pre-Installation Verification

Step	Check	Required evidence
1	Identity	Match every character of 6ES7288-2DT16-0AA0 to the physical label; record revision and serial data.
2	Host system	Confirm rack, slot, CPU/drive/controller, firmware, project, and machine-builder approval.
3	Electrical	Verify supply, signal type, channel limits, grounding, shielding, and connector pinout from the exact Siemens document.
4	Mechanical	Confirm form factor, keying, mounting, clearances, cable routing, and environmental limits.
5	Lifecycle	The exact article number is documented in Siemens official S7-200 SMART ordering information and technical documentation; confirm current regional availability at quotation.
6	Commissioning	Apply the original test procedure and record results before returning the equipment to service.

Product-Specific Precautions

- Identity: Match every character of 6ES7288-2DT16-0AA0 and the SM DT16 marking to the physical nameplate and project
- Power: Verify 24 V DC nominal; 20.4 to 28.8 V DC permissible; isolate all energy sources before wiring, insertion, or removal
- Signals: Observe every input/output voltage, current, common, group, polarity, isolation, and protective-device limit
- Panel: Use documented DIN-rail mounting, clearances, protective earth, cable segregation, ventilation, and IP20 enclosure protection
- Commissioning: Back up the project, verify addresses and terminals, test one circuit group at a time, and record the results

2. Commissioning Record

Record item	Site entry
Physical model / MLFB	
Serial or revision	
Host system / machine	
Rack / slot / location	
Firmware / project backup	
Connector and wiring verified	
Functional test result	
Technician / date	

Source Basis

Siemens official technical data sheet for 6ES7288-2DT16-0AA0: <https://support.industry.siemens.com/teddatasheet/?caller=SIO&format=pdf&language=en&mlfb=6ES7288-2DT16-0AA0>; Siemens official S7-200 SMART ordering information: https://www.ad.siemens.com.cn/download/documentdetail_17711.html; Siemens official system manual with model-specific I/O tables: https://support.industry.siemens.com/cs/attachments/109963390/SIMATIC_ET_200_SMART_IM60_System_Manual_en-US.pdf

Important Notice

This Apter Power checklist is not a Siemens installation instruction. The current Siemens documentation, the physical nameplate, the host-equipment manual, and applicable safety rules control all work.

APTER POWER SALES TEAM


INDUSTRIAL AUTOMATION PRODUCT SUPPORT

Eight sensed states. Eight fast commands. One compact I/O bridge.

WHATSAPP / PHONE +86 180 3023 5313

EMAIL sales13@apterpower.com

WEBSITE www.apterpower.com



SCAN FOR PRODUCT & QUOTE

6ES7288-2DT16-0AA0