

APTER POWER INSTALLATION & VERIFICATION REFERENCE

84508-30

A separate product-specific field checklist

Use this model-specific reference to verify the complete Bently Nevada ordering code, matched components, mounting geometry, signal path, and approval evidence before installation or substitution.


Manufacturer	Bently Nevada
Prepared by	Apter Power
Document ID	AP-BN-B10-10-84508-30-IV-R1
Revision	R1
Issue date	2026-08-20

APTER POWER SALES TEAM

INDUSTRIAL AUTOMATION PRODUCT SUPPORT

Thirty feet of shielded high-temperature signal continuity.

WHATSAPP / PHONE +86 180 3023 5313
EMAIL sales13@apterpower.com
WEBSITE www.apterpower.com



SCAN FOR PRODUCT & QUOTE
84508-30

1. Pre-Installation Verification

Step	Check	Required evidence
1	Identity	Match every character of 84508-30 to the physical nameplate and quotation.
2	Mechanical	Ordered length: 30 ft (about 9.0 m). Exact configured weight, cable diameter, and packed-carton dimensions are not published.
3	System matching	Bently Nevada 74712 or 9200 Seismoprobe Velocity Transducers when the installation calls for lug-to-lug high-temperature cable.
4	Signal path	It carries the self-generated velocity signal from a 9200 or 74712 Seismoprobe installation through high-temperature field routing to terminal points, a monitor, or an intermediate junction. The shield controls electrical noise while the two conductors preserve the sensor's differential signal and polarity.
5	Approval	Use only the approvals and installation drawing confirmed by the exact physical marking.
6	Commissioning	Record gap, loop or monitor scaling, functional test result, technician, and date.

Product-Specific Precautions

- Confirm that 30 ft is the required route length before installation; avoid hidden coils that add heat exposure or noise pickup.
- Verify both terminal-lug sizes, conductor polarity, shield termination, and monitor input wiring against the current diagram.
- Protect the unarmored cable in suitable conduit or mechanical protection and support it away from sharp edges and hot surfaces beyond its rating.
- Do not substitute 84508 for an armored 84509 or connector-ended 84660/84510 cable without checking the complete interface.
- Perform continuity, insulation, shield, and end-to-end signal checks before returning the monitoring channel to service.

2. Commissioning Record

Record item	Site entry
Physical model / suffix	
Serial / revision	
Machine and measurement point	
Matched cable / sensor / transmitter	
Mounting and gap evidence	
Signal or loop scaling	
Approval drawing / barrier	
Functional test result	
Technician / date	

Source Basis

Baker Hughes / Bently Nevada 9200 and 74712 Seismoprobe Velocity Transducers Datasheet 141626 Rev. V - <https://dam.bakerhughes.com/m/7b3b66d04b57d922/original/9200-and-74712-Seismoprobe-Velocity-Transducers-Datasheet-141626-pdf.pdf>

Important Notice

This Apter Power checklist is not a Bently Nevada installation instruction. The current manufacturer documentation, the physical nameplate, the machine drawing, and applicable safety rules control all work.

APTER POWER SALES TEAM

INDUSTRIAL AUTOMATION PRODUCT SUPPORT

Thirty feet of shielded high-temperature signal continuity.

WHATSAPP / PHONE +86 180 3023 5313

EMAIL sales13@apterpower.com

WEBSITE www.apterpower.com



SCAN FOR PRODUCT & QUOTE

84508-30