

80363975-100

PM/APM/HPM/EHPM I/O Cardfile

Honeywell 80363975-100 is an I/O cardfile for Process Manager-family systems. It houses configured I/O processors and provides their cabinet backplane connections.

APTER POWER SALES TEAM

WHATSAPP / PHONE +86 180 3023 5313
EMAIL sales13@apterpower.com
WEBSITE www.apterpower.com



SCAN FOR PRODUCT & QUOTE

80363975-100

PRODUCT SNAPSHOT

BRAND

Honeywell

FAMILY

TPS Process Manager I/O

MODEL

80363975-100

DOCUMENT SET

Technical reference / field workbook / complete information

OFFICIAL PRODUCT DESCRIPTION

Honeywell 80363975-100 is an I/O cardfile for Process Manager-family systems. It houses configured I/O processors and provides their cabinet backplane connections.

FUNCTION MAP



TECHNICAL DATA

CARDFILE CAPACITY 15 I/O processor positions	SYSTEM FAMILY PM; APM; HPM; EHPPM
MOUNTING Cabinet cardfile	PRIMARY FUNCTION I/O processor housing
BACKPLANE ROLE I/O link distribution	POSITIONING Keyed processor slots

ENGINEERING NOTE

Label every processor position and cable before removal, inspect the backplane and restore each I/O processor to its original keyed slot.

COMMON APPLICATIONS

1

Process Manager I/O cabinets

2

APM/HPM cardfile maintenance

3

I/O processor replacement

4

Legacy TPS cabinet restoration

COMPATIBILITY REVIEW

IDENTITY Exact model and hardware execution: 80363975-100	HOST PLATFORM TPS Process Manager I/O
PRIMARY COMPANION PM/APM/HPM/EHPM controller	SECONDARY COMPANION I/O processors
FIELD BOUNDARY Cardfile power system	ACCEPTANCE DUTY Process Manager I/O cabinets

MANUFACTURER SOURCE RECORD

Honeywell Experion Control Hardware Planning Guide | PM I/O cardfile hardware

Selection boundary: never transfer ratings, wiring, configuration or compatibility from a visually similar model. Confirm the complete physical label and the manufacturer record for the installed system.

PRODUCT PRECAUTIONS

- 1

Verify the complete 80363975-100 marking, hardware execution and assigned TPS Process Manager I/O position.
- 2

Place the process in the approved maintenance state and isolate every applicable energy source.
- 3

Record as-found wiring, shields, jumpers, cable tags, slot identity and diagnostics before removing 80363975-100.
- 4

Use ESD controls and protect keyed connectors, terminals and assemblies while handling 80363975-100.
- 5

Confirm the installed PM/APM/HPM/EHPM controller and I/O processors against approved drawings and configuration records.
- 6

Inspect mating hardware, terminal condition, grounding and mechanical retention before installation.
- 7

Restore power or network service in controlled stages; confirm status indications before functional commands.
- 8

Complete a documented functional test for process manager i/o cabinets and retain the as-left record.

COMMISSIONING ACCEPTANCE

MECHANICAL Correct position, retention and terminal condition	ELECTRICAL / NETWORK Supply, grounding, shields, polarity and continuity confirmed
CONFIGURATION Slot, channel, range and companion hardware match approved records	FUNCTIONAL Controlled process manager i/o cabinets test completed without abnormal diagnostics

Related TPS Process Manager I/O products on Apter Power

MODEL	SERIES / SYSTEM ROLE	APTER POWER PAGE
80363975-150	MC-PDOY22 32-point digital-output processor	Open product page
80363972-100	TPS Process Manager-family I/O hardware	Open product page
80363972-150	TPS Process Manager-family I/O hardware	Open product page
MC-PAOY22 80363969-150	Process Manager analog-output processor	Open product page
K2LCN-8	TPS node processor board with LCN interface	Open product page

ENGINEER FAQ — 8 MODEL-SPECIFIC CHECKS

Q1	What must be matched before installation?	Match the full 80363975-100 marking, revision or execution, assigned position and installed companion hardware.
Q2	What should be isolated first?	Use the site's approved maintenance state and isolate the energy sources serving PM/APM/HPM/EHPM controller and I/O processors.
Q3	What as-found record is required?	Record terminal identity, polarity, shields, jumpers, cable tags, configuration and diagnostic status.
Q4	Which compatibility check is mandatory?	Compare the TPS Process Manager I/O slot, interface, companion hardware and wiring scheme with approved project documentation.
Q5	How should commissioning begin?	Begin with visual and continuity checks, then restore service in stages and observe normal status indications.
Q6	How should the assigned function be proved?	Use a controlled test for process manager i/o cabinets while required interlocks and process safeguards remain effective.
Q7	What should be checked after an abnormal result?	Recheck seating, terminations, supply or network condition, channel assignment and manufacturer diagnostics before further replacement.
Q8	What evidence should be retained?	Retain the 80363975-100 identity, as-left wiring/configuration, final diagnostics and functional-test result.

MANUFACTURER SOURCE RECORD

Honeywell Experion Control Hardware Planning Guide | PM I/O cardfile hardware