

# 900B01-0101

## Four-Channel Analog Output Module

Honeywell 900B01-0101 is a four-channel HC900 analog output module. It supplies isolated 0–20 mA control signals to connected final elements.

### APTER POWER SALES TEAM

WHATSAPP / PHONE +86 180 3023 5313  
EMAIL sales13@apterpower.com  
WEBSITE www.apterpower.com



SCAN FOR PRODUCT & QUOTE

900B01-0101

### PRODUCT SNAPSHOT

#### BRAND

Honeywell

#### FAMILY

HC900 Process Controller

#### MODEL

900B01-0101

#### DOCUMENT SET

Technical reference / field workbook / complete information

OFFICIAL PRODUCT DESCRIPTION

Honeywell 900B01-0101 is a four-channel HC900 analog output module. It supplies isolated 0–20 mA control signals to connected final elements.

FUNCTION MAP



TECHNICAL DATA

|                                               |                                                   |
|-----------------------------------------------|---------------------------------------------------|
| <b>OUTPUT CHANNELS</b><br>4                   | <b>OUTPUT RANGE</b><br>0–20 mA                    |
| <b>OUTPUT ISOLATION</b><br>Channel isolated   | <b>CONTROLLER FAMILY</b><br>HC900                 |
| <b>SIGNAL DOMAIN</b><br>Analog current output | <b>INSTALLATION FORM</b><br>HC900 rack I/O module |

ENGINEERING NOTE

Verify channel scaling and loop polarity with final elements secured, then test each output from a low command to the intended operating range.

COMMON APPLICATIONS

1

Control-valve commands

2

Drive speed references

3

Dosing-pump setpoints

4

Process damper positioning

COMPATIBILITY REVIEW

|                                                                    |                                                  |
|--------------------------------------------------------------------|--------------------------------------------------|
| <b>IDENTITY</b><br>Exact model and hardware execution: 900B01-0101 | <b>HOST PLATFORM</b><br>HC900 Process Controller |
| <b>PRIMARY COMPANION</b><br>HC900 I/O rack                         | <b>SECONDARY COMPANION</b><br>HC900 controller   |
| <b>FIELD BOUNDARY</b><br>Current-loop field wiring                 | <b>ACCEPTANCE DUTY</b><br>Control-valve commands |

**MANUFACTURER SOURCE RECORD**

Honeywell HC900 Process Controller Installation and User Guide | 51-52-25-107 Revision 18

Selection boundary: never transfer ratings, wiring, configuration or compatibility from a visually similar model. Confirm the complete physical label and the manufacturer record for the installed system.

PRODUCT PRECAUTIONS

- 1

Verify the complete 900B01-0101 marking, hardware execution and assigned HC900 Process Controller position.
- 2

Place the process in the approved maintenance state and isolate every applicable energy source.
- 3

Record as-found wiring, shields, jumpers, cable tags, slot identity and diagnostics before removing 900B01-0101.
- 4

Use ESD controls and protect keyed connectors, terminals and assemblies while handling 900B01-0101.
- 5

Confirm the installed HC900 I/O rack and HC900 controller against approved drawings and configuration records.
- 6

Inspect mating hardware, terminal condition, grounding and mechanical retention before installation.
- 7

Restore power or network service in controlled stages; confirm status indications before functional commands.
- 8

Complete a documented functional test for control-valve commands and retain the as-left record.

COMMISSIONING ACCEPTANCE

|                                                                                            |                                                                                                    |
|--------------------------------------------------------------------------------------------|----------------------------------------------------------------------------------------------------|
| <b>MECHANICAL</b><br>Correct position, retention and terminal condition                    | <b>ELECTRICAL / NETWORK</b><br>Supply, grounding, shields, polarity and continuity confirmed       |
| <b>CONFIGURATION</b><br>Slot, channel, range and companion hardware match approved records | <b>FUNCTIONAL</b><br>Controlled control-valve commands test completed without abnormal diagnostics |

Related HC900 Process Controller products on Apter Power

| MODEL       | SERIES / SYSTEM ROLE                        | APTER POWER PAGE                  |
|-------------|---------------------------------------------|-----------------------------------|
| 900B08-0202 | HC900 900B-series analog module             | <a href="#">Open product page</a> |
| 900G02-0102 | 16-channel 24 Vdc digital input module      | <a href="#">Open product page</a> |
| 900G03-0102 | 16-channel 120/240 Vac digital input module | <a href="#">Open product page</a> |
| 900H03-0102 | 8-channel 120/240 Vac digital output module | <a href="#">Open product page</a> |
| 900H02-0202 | HC900 900H-series output module             | <a href="#">Open product page</a> |

ENGINEER FAQ — 8 MODEL-SPECIFIC CHECKS

|    |                                                  |                                                                                                                                         |
|----|--------------------------------------------------|-----------------------------------------------------------------------------------------------------------------------------------------|
| Q1 | What must be matched before installation?        | Match the full 900B01-0101 marking, revision or execution, assigned position and installed companion hardware.                          |
| Q2 | What should be isolated first?                   | Use the site's approved maintenance state and isolate the energy sources serving HC900 I/O rack and HC900 controller.                   |
| Q3 | What as-found record is required?                | Record terminal identity, polarity, shields, jumpers, cable tags, configuration and diagnostic status.                                  |
| Q4 | Which compatibility check is mandatory?          | Compare the HC900 Process Controller slot, interface, companion hardware and wiring scheme with approved project documentation.         |
| Q5 | How should commissioning begin?                  | Begin with visual and continuity checks, then restore service in stages and observe normal status indications.                          |
| Q6 | How should the assigned function be proved?      | Use a controlled test for control-valve commands while required interlocks and process safeguards remain effective.                     |
| Q7 | What should be checked after an abnormal result? | Recheck seating, terminations, supply or network condition, channel assignment and manufacturer diagnostics before further replacement. |
| Q8 | What evidence should be retained?                | Retain the 900B01-0101 identity, as-left wiring/configuration, final diagnostics and functional-test result.                            |

MANUFACTURER SOURCE RECORD

Honeywell HC900 Process Controller Installation and User Guide | 51-52-25-107 Revision 18