Siemens 39SDM024DCCBN 16101-174R/12

Discrete I/O Module

APACS+ Standard Discrete 24 V module identified for discrete process-signal service; the 16101-174R/12 marking is preserved as supplied.

Job objective

Replace, install or verify the exact module without changing unrelated wiring, configuration, dimensions, weight or other stored product data.

Safe-work boundary

Identify Match the complete model and every suffix or secondary code.	**Isolate** Apply the plant-approved electrical and process isolation procedure.
Preserve Back up configuration and photograph all connections.	**Control** Use ESD protection and revision-controlled documentation.

Required evidence before work

Nameplate photo; slot/rack record; connector map; project backup where applicable; fault history; approved acceptance procedure.

Readiness checklist

Exact identity	Siemens 39SDM024DCCBN 16101-174R/12 matches the work order and physical unit
System position	Rack, slot and functional assignment are recorded
Configuration	Parameters, firmware or project data are backed up when applicable
Connections	Every cable, terminal, jumper and shield is labeled
Condition	Connector, board and packaging condition are inspected
Test plan	Expected states and acceptance evidence are agreed

Interface preparation

APACS+ rack	Backplane and module-bus connection
Field termination	24 V discrete circuits; verify exact point assignment
Channel commons	Confirm against the /12 assembly drawing
Status indication	Interpret with the exact revision documentation

03 / INSTALLATION SEQUENCE

Controlled replacement workflow

1	Confirm isolation and absence of hazardous energy
2	Compare old and replacement identities and revisions
3	Photograph and label all connections
4	Remove the existing module using ESD-safe handling
5	Inspect slot, connector, grounding and cooling path
6	Install the exact replacement without forcing connectors
7	Restore cables, jumpers and settings from the controlled record
8	Perform a final visual and continuity check before energization

STOP POINT

Do not energize if the model, slot, connector orientation, grounding, jumper state or documented system assignment is unresolved.

Staged return to service

Stage	Action	Acceptance
Stage 1	Visual inspection and isolation release	Expected controlled result
Stage 2	Apply control power under observation	Expected controlled result
Stage 3	Confirm module recognition or status	Expected controlled result
Stage 4	Verify communication and affected signal paths	Expected controlled result
Stage 5	Exercise the documented function	Expected controlled result
Stage 6	Archive measured results and as-left configuration	Expected controlled result

Product-specific acceptance focus

1

Do not infer channel count or direction from /8, /10 or other suffixes.

2

Verify each common, field supply and termination point.

3

Inspect the rack connector and field terminal assembly.

4

Test every affected discrete point before process release.

Fault isolation and final record

1	Unexpected state: stop and capture evidence
2	Recheck identity, power, slot and connectors
3	Compare configuration and revision records
4	Test surrounding system before condemning the module
5	Restore a safe state and document the outcome

Apter Power handover record

Model identity	Keep the complete Siemens model code and every suffix in purchasing, installation and acceptance records.
Verification boundary	Confirm the physical nameplate, installed position and revision-controlled project documents before field work.
Apter Power support	Use the contact details and Apter Power website links in this document for product and sourcing support.

Related Apter Power references	Scope note
Siemens 39SDM024DCCBN 16101-174/8	Portfolio reference only; verify compatibility independently.
Siemens 16101-174/10	Portfolio reference only; verify compatibility independently.

Commissioning support sales7@apterpower.com +86 180 3017 5807 www.apterpower.com