FIELD WORKFLOW

Schneider Electric 140ACI03000C

eight-channel multirange analogue input module

The module applies a 15 Hz single-pole low-pass filter, channel diagnostics and defined isolation to eight multirange analogue inputs.

Release-gate sequence

1. IDENTIFY
2. ISOLATE
3. INSTALL
4. STATIC CHECK
5. FUNCTION TEST
6. ACCEPT

Before work starts

- Confirm the complete Schneider Electric 140ACI03000C identity before isolation.
- Record Product range: Modicon Quantum automation platform, Product type: Analogue input module, Analogue inputs: 8 differential channels.
- Photograph the installed position, connector orientation, cable labels and visible indicators.
- Capture the active channel map, network settings, alarm logic or rack-population record that applies to this item.
- Place affected equipment in the approved safe maintenance condition.
- Prepare calibrated test equipment and the exact-model acceptance record.

Field record essentials

MODEL ID

Record 140ACI03000C exactly.

SYSTEM

Accepts the configured 1–5 V or 4–20 mA signal at each differential channel.

SETTINGS

Preserve the verified installed configuration.

TEST BASIS

Define static and functional acceptance evidence.

Pre-installation verification

CHECK 01

Confirm the complete Schneider Electric 140ACI03000C identity before isolation.

CHECK 02

Record Product range: Modicon Quantum automation platform, Product type: Analogue input module, Analogue inputs: 8 differential channels.

CHECK 03

Photograph the installed position, connector orientation, cable labels and visible indicators.

CHECK 04

Capture the active channel map, network settings, alarm logic or rack-population record that applies to this item.

CHECK 05

Place affected equipment in the approved safe maintenance condition.

CHECK 06

Prepare calibrated test equipment and the exact-model acceptance record.

Interface inventory

- Field signal: Accepts the configured 1–5 V or 4–20 mA signal at each differential channel.
- Input conditioning: Applies the 15 Hz low-pass filter and 12-bit conversion.
- Quantum backplane: Transfers nine input words and module diagnostics to the controller.
- Control application: Uses scaled values and channel status within the approved program.

Hold point

Do not continue if the complete model, field-circuit identity, stored settings, protective functions or safe isolation state cannot be verified. Preserve existing wiring records and escalate the exact unresolved item.

Installation sequence

1. Match the replacement label to Schneider Electric 140ACI03000C and the approved hardware record.
2. Review the recorded wiring, interfaces, rack position and configuration before disturbing hardware.
3. Isolate hazardous energy and prove the required electrical condition at the work point.
4. Apply grounded ESD controls while handling the electronic assembly or backplane connection.
5. Label and remove cables or conductors without changing their established order or path.
6. Inspect terminals, connectors, guides, latches, sealing and mounting hardware for damage or contamination.
7. Seat and secure the exact article without forcing connectors; restore each interface to its recorded position.
8. Re-energize under the approved sequence and review hardware, channel, power or network diagnostics.

Commissioning and acceptance

GATE 1

Verify the installed identity remains Schneider Electric 140ACI03000C after energization.

GATE 2

Compare restored interfaces, channel assignments or rack population with the approved engineering record.

GATE 3

Apply traceable input values to every serviced channel and compare the raw value, engineering scaling and diagnostic state.

GATE 4

Check alarm, diagnostic and fault responses without defeating required protective functions.

GATE 5

Confirm adjacent modules and unaffected channels or network drops continue to operate normally.

GATE 6

Inspect connectors, terminals, cable strain, unusual temperature, odor and visible indications during the test.

GATE 7

Record measured values, software indications, diagnostic events and corrective actions.

GATE 8

Obtain the required engineering or operations acceptance before service release.

Fault-response checks

- An incorrect or unstable input requires checks of source range, polarity, loop power, terminal assignment, shielding, scaling and channel status.
- Intermittent behavior: inspect seating, connector retention, shielding, grounding and vibration exposure.
- Wrong point or position: reconcile the physical slot, terminal or network identity with the controller and drawing.
- Persistent diagnostic: compare the as-left condition with the captured pre-maintenance baseline.
- Neighboring faults: inspect shared backplane power, common conductors, cable paths and adjacent interfaces.
- Repeat failure: stop substitution and escalate the exact identity, evidence and test record for engineering review.

Acceptance boundary

Release only after the normal state, commanded state, principal fault state and recovery behavior have all been observed at the field device, module and control-system indication.

Reference and handover

SOURCE 1	140ACI03000C official product data sheet
SOURCE 2	Modicon Quantum analogue I/O wiring information

Related products

Verified related products on ApterPower

Schneider Electric 140DDI35310

Quantum discrete-input module

View Schneider Electric 140DDI35310

CONFIGURATION

Final settings and mappings archived

WIRING

Terminal and conductor labels reconciled

TEST RECORD

Measured results and fault tests retained

OPERATIONS

Normal indication and response briefed

Contact Apter Power

PHONE +86 180 3023 5313

EMAIL sales13@apterpower.com

WEBSITE www.apterpower.com

Share the exact 140ACI03000C nameplate, application and required quantity for a model-specific quotation.