General Electric DS200SLCCG1AFG

Installation and verification guide

General Electric DS200SLCCG1AFG is a lan communication card for the GE Mark V control. It provides the local-area-network communication interface for a compatible Mark V drive or control assembly.

Complete reference	DS200SLCCG1AFG
Product type	LAN Communication Card
Platform	GE Mark V control
Technical basis	GE Mark V control-system hardware documentation and exact-board identification records

Product page
https://www.apterpower.com/General-Electric/Gas-Turbine-Control/ds200slccg1afg

WhatsApp / technical contact
sales13@apterpower.com | +86 18030235313

01 Installed-hardware capture

The complete DS200SLCCG1AFG marking establishes the offered identity. Record all labels, connector positions and installed associations before removal because adjacent GE Mark V control references may differ in wiring, option content or revision compatibility.

Buyer reference	Send the complete DS200SLCCG1AFG marking, revision or option label, connector photographs and installed application details.
Offer comparison	Compare the offered DS200SLCCG1AFG with the installed lan communication card, termination hardware and approved General Electric documentation before ordering.

02 Configuration and connector controls

Confirm the complete marking	Do not shorten DS200SLCCG1AFG or transfer data from an adjacent reference.
Record every connection	Photograph connector orientation and label each cable or terminal before removal.
Preserve the configuration	Retain the approved GE Mark V control database, jumpers, switches or channel assignment as applicable.
Apply controlled isolation	Follow the site energy-isolation and ESD procedure before disturbing hardware.
Verify companion hardware	Check the documented base, cable, terminal, power and partner-module relationship.
Prove the restored function	Complete visual, electrical and functional checks before return to automatic service.

03 Controlled functional verification

During replacement, preserve the approved configuration and connection map. Perform a controlled visual, electrical and functional check, record the as-left result, and release the equipment only after the responsible site authority accepts the restored lan communication card.

01	Send the full DS200SLCCG1AFG reference, label photographs and required quantity.
02	Apply site-approved isolation and ESD controls.
03	Record connectors, terminals and configuration before removal.
04	Compare the offered hardware with the complete installed reference.
05	Install without forcing connectors or changing approved routing.

06	Restore configuration and perform controlled checks.
07	Review revision, condition, included items and connection compatibility for DS200SLCCG1AFG.
08	Confirm quantity, dispatch date and delivery details for DS200SLCCG1AFG in the quotation.

04 Product-specific engineering questions

Which identity fields must match before installing DS200SLCCG1AFG?	Match the complete model, group, revision, connector layout and any programmed or option-specific devices with the installed record.
How should connector positions on DS200SLCCG1AFG be documented?	Photograph and label each connector before removal, then compare keyed positions and cable destinations against the approved drawing.
What configuration must be retained when replacing DS200SLCCG1AFG?	Retain switch or jumper positions, firmware or programmable-device identity and the system database or drive setup that governs the board.
How can a system fault be separated from a DS200SLCCG1AFG board fault?	Review diagnostics, power rails, connectors and companion hardware, then use an approved substitution or bench method without bypassing protection.
Why must the full revision of DS200SLCCG1AFG be reviewed?	Revision letters can reflect hardware or firmware compatibility boundaries; confirm interchangeability for the installed system before release.
What cleaning restrictions apply to DS200SLCCG1AFG?	Use an approved ESD-safe method, keep solvents away from labels and programmed devices, and do not disturb conformal coating or adjustments.
What controlled startup checks apply after fitting DS200SLCCG1AFG?	Verify supply rails, status indications, communication and the board-specific control function in the approved sequence before automatic operation.
What service evidence should be retained for DS200SLCCG1AFG?	Retain complete markings, revision, connector mapping, configuration records, diagnostic results and as-left functional acceptance.

05 Handover evidence

Identity	Complete marking, revision and photographs
Connection	Terminal or connector map and cable destinations
Configuration	Approved database, settings or option record
Functional proof	As-found and as-left readings or diagnostic results
Acceptance	Responsible technician and release approval

06 Related service references

General Electric DS200UPSAG1AFD	UC2000 Power Supply Board
General Electric DS200UPSAG1AGD	UC2000 Power Supply Board
General Electric DS6800CCID1D1D	Industrial Control Printed Circuit Board
General Electric DS200TCEAG1BTF	Emergency Overspeed Board
General Electric DS200CPCAG1ABB	Contactor Pilot Board